



**Northern Region
South East Queensland
Joint Regional Councils**

Specification No. C241



**QUEENSLAND
DEVELOPMENT
CONSTRUCTION
SPECIFICATION**

C241

STABILISATION



Cooloolool Shire Council



Noosa Council

Contract No.

STABILISATION

QUEENSLAND

DEVELOPMENT CONSTRUCTION SPECIFICATION

C241

STABILISATION

These Specifications have been tailored from the AusSpec Standard Specifications for use within Pine Rivers Shire Council, and in consultation with the Northern Region, South East Queensland, group of Councils.

This group includes Pine Rivers Shire, Redcliffe City, Caboolture Shire, Caloundra City, Maroochy Shire, Noosa Council and Cooloolool Shire.



Contract No.



Cooloola Shire Council



Noosa Council

STABILISATION

Amendment Record for this Specification Part

This Specification is Council's edition of the AUS-SPEC generic specification part and includes Council's primary amendments.

Details are provided below outlining the clauses amended from the Council edition of this AUS-SPEC Specification Part. The clause numbering and context of each clause are preserved. New clauses are added towards the rear of the specification part as special requirements clauses. Project specific additional script is shown in the specification as italic font.

The amendment code indicated below is 'A' for additional script 'M' for modification to script and 'O' for omission of script. An additional code 'P' is included when the amendment is project specific.

Amendment Sequence No.	Key Topic addressed in amendment	Clause No.	Amendment Code	Author Initials	Amendment Date
<i>EXAMPLE 1</i>	<i>Provision for acceptance of nonconformance with deduction in Payment</i>	<i>XYZ.00</i>	<i>AP</i>	<i>KP</i>	<i>2/6/97</i>
1	SCOPE	C241.01 Parts 1 & 4	M	LDP/ DKM	4/9/02
2	REFERENCE DOCUMENTS	C241.02 Part 1(a)	M	LDP/ DKM	4/9/02
3	MATERIALS PROPOSED FOR USE IN THE WORK	C241.03 Part 1	M	LDP/ DKM	4/9/02
4	MIXING	C241.14 (b) Part 4		LDP/ DKM	4/9/02
5	TRIMMING AND COMPACTION	C241.16 Parts 1 & 5	M	LDP/ DKM	4/9/02
6	Pay Items	C241.24 Part 3	M	LDP/ DKM	4/9/02



Contract No.



Cooloola Shire Council



Noosa Council

STABILISATION

**NORTHERN REGION SOUTH EAST QUEENSLAND
JOINT REGIONAL COUNCILS
QUEENSLAND DEVELOPMENT CONSTRUCTION
SPECIFICATION C241 – STABILISATION**

INDEX

CLAUSE	CONTENTS	PAGE
GENERAL INFORMATION		1
C241.01	Scope	1
C241.02	Reference Documents	2
INSPECTION, SAMPLING AND TESTING		2
C241.03	Materials Proposed for Use in the Work	2
C241.04	Materials Used in the Work	3
MATERIALS.....		3
C241.05	Cement	3
C241.06	Quicklime	3
C241.07	Hydrated Lime	4
C241.08	Ground Granulated Blast Furnace Slag	4
C241.09	Flyash	4
C241.10	Blended Stabilising Agents	5
C241.11	Water	5
STABILISATION PROCEDDES		5
C241.12	General	5
C241.13	Application of Stabilisation Agent	6
C241.14	Mixing	7
C241.15	Field Working Period	8
C241.16	Trimming and Compaction	8
C241.17	Joints	9
C241.18	Tolerances	10
C241.19	Curing	10
LIMITS AND TOLERANCES.....		11
C241.20	Summary of Limits and Tolerances	11
SPECIAL REQUIREMENTS.....		13
C241.21	Reserved	13
C241.22	Reserved	13
C241.23	Reserved	13



Contract No.



Cooloola Shire Council



Noosa Council

STABILISATION

**NORTHERN REGION SOUTH EAST QUEENSLAND
JOINT REGIONAL COUNCILS
QUEENSLAND DEVELOPMENT CONSTRUCTION
SPECIFICATION C241 – STABILISATION**

INDEX

CLAUSE	CONTENTS	PAGE
MEASUREMENT AND PAYMENT		13
C241.24	Pay Items.....	13
C241.24a	Supply and Spread Stabilising Agent (In-Situ Mixing Only).....	13
C241.24b	Mixing of Stabilising Agent	14
ANNEXURE		15
C241.a	Stabilisation Mix Design	15



Contract No.



Coooloolo Shire Council



Noosa Council

STABILISATION**SPECIFICATION C241
STABILISATION****GENERAL INFORMATION****C241.01 SCOPE**

- Where specifically permitted by Council, this Specification defines the requirements for stabilised materials provided by stationary plant production as well as materials and process requirements for in-situ stabilisation.
- The work to be executed under this Specification consists of the supply and incorporation of stabilising binders with material in a nominated pavement course or subgrade layer (including materials for the selected material zone, and selected backfill), at specified locations in the work and the spreading, compaction, trimming and curing of such materials.
- This Specification provides the requirements for stabilisation of the types of pavement courses and subgrade zones or layers as shown in Table C241.1.

Scope

Pavement Course Or Subgrade Zone Or Layer	Stabilising Binder
PAVEMENT COURSE	
Base and Subbase	Cement Blended Stabilising Agent Hydrated Lime (pugmill) Quicklime (in-situ)
SUBGRADE ZONE OR LAYER	
Selected Material Zone	Cement Blended Stabilising Agent Quicklime (in-situ) Hydrated Lime (pugmill)
Other Subgrade Layers	Cement Blended Stabilising Agent Quicklime (in-situ) Hydrated Lime (pugmill)
Selected Backfill Zone	Cement Hydrated Lime (pugmill)

Table C241.1
Types Of Pavement Courses, Subgrade Zones
Or Layers And Stabilising Binder

- The pavement course or subgrade zone or layer to be stabilised shall be as specified in the Specifications for MRS11.05 UNBOUND PAVEMENTS, or as indicated on the Drawings.
- Requirements for quality control and testing, including maximum lot sizes and minimum test frequencies, are cited in the Specification Part for Quality Control Requirements.

Associated Specifications**Quality**



Contract No.

STABILISATION

C241.02 REFERENCE DOCUMENTS

1. Documents referenced in this Specification are listed in full below whilst being cited in the text in the abbreviated form or code indicated.

**Documents
Standards Test
Methods**

(a) Council Specifications

C201	-	Control of Traffic
C211	-	Control of Erosion and Sedimentation
C213	-	Earthworks
C220	-	Stormwater Drainage – General
MRS11.05	-	Unbound Pavements

(b) Australian Standards

AS 1141.11	-	Particle size distribution by dry sieving.
AS 1289.5.7.1	-	Compaction control test (Rapid method)
AS 1289.5.8.1	-	Determination of field density and field moisture content of a soil using a nuclear surface moisture-density gauge - Direct transmission mode
AS 1289.4.2.1	-	Determination of the sulphate content of a natural soil and the sulphate content of the ground water - Normal Method.
AS 1289.6.1.1	-	Determination of the California bearing ratio of a soil - Standard laboratory method for a remoulded specimen.
AS 2350.4	-	Setting time of Portland and blended cements.
AS 2350.9	-	Fineness of Portland fly ash cement.
AS 3582.1	-	Fly ash.
AS 3582.2	-	Slag - Ground granulated iron blastfurnace.
AS 3583.3	-	Determination of loss on ignition.
AS 3583.6	-	Determination of relative water requirement and relative strength.
AS 3583.12	-	Determination of available alkali.
AS 3583.13	-	Determination of chloride ion content.
AS 3583.14	-	Determination of insoluble residue content
AS 3972	-	Portland and blended cements

(c) NSW RTA Test Methods

T432	-	Rate of Slaking of Quicklime
------	---	------------------------------

INSPECTION, SAMPLING AND TESTING

C241.03 MATERIALS PROPOSED FOR USE IN THE WORK

1. The Contractor shall provide a certificate from a laboratory with appropriate NATA registration stating that the stabilisation mix(s) submitted and the mix constituents comply with the mix nominated in Annexure C241A and that the stabilised material meets the requirements of the

**Contractor's
Responsibility**



Noosa Council

Contract No.

STABILISATION

C241.03 MATERIALS PROPOSED FOR USE IN THE WORK cont.

Specification for MRS11.05 UNBOUND PAVEMENTS if incorporated into the works as a pavement layer or alternatively the Specification for EARTHWORKS or STORMWATER DRAINAGE GENERAL.

C241.04 MATERIALS USED IN THE WORK

1. Regular inspection, sampling and testing of pavement and subgrade materials shall be undertaken by the Contractor while stabilisation is in progress in accordance with this Specification.

Sampling and Testing

MATERIALS

C241.05 CEMENT

1. The type of cement used as the stabilising agent or a constituent in a blended stabilising agent shall comply with AS 3972.
2. Cement shall be from a source approved under the Queensland Government's State Purchasing Policy at time of production.
3. The Contractor shall nominate the brand and source of all cementitious materials.
4. Documentary evidence of the quality and source of the cement shall be furnished by the Contractor to the Superintendent upon request at any time.
5. If the Contractor proposes to use cement which has been stored for a period in excess of three months from the time of manufacture, the Contractor shall arrange a re-test, to ensure the cement still complies with AS3972, before the cement is used in the work. The cost of retesting cement, which has been stored for a period in excess of three months, shall be borne by the Contractor. Test results shall be forwarded to the Superintendent for approval at least 2 days in advance of usage of the material.

Type

Nominated Brand and Source

Proof of Quality

Storage in Excess of 3 months

C241.06 QUICKLIME

1. Quicklime, consisting essentially of calcium oxide in a highly reactive form, shall have the following properties at the point of spread:
 - (i) Available Lime The content of calcium oxide, determined by AS 3583.12, shall not be less than 85 per cent.
 - (ii) Slaking Rate The active slaking time shall not be greater than twenty minutes and the temperature rise on slaking, determined from the average of four samples tested in accordance with Test Method T432, shall not be less than 40°C in six minutes.
2. The particle size distribution of the quick lime determined by AS 1141.11 shall comply with the following requirements in Table C241.2.

Properties

Particle Size

**C241.06 QUICKLIME cont.**

AS Sieve	Per Cent Passing
13.2mm	100
9.5mm	96 - 100
4.75mm	70 - 100
2.36mm	0 - 90

Table C241.2
Particle Size Distribution of Quicklime

C241.07 HYDRATED LIME

1. Hydrated lime, consisting essentially of calcium hydroxide, whether used as the sole stabilising agent or blended with other additives, shall have the following properties:

Properties

- (i) Available Lime The content of calcium hydroxide, determined by AS 3583.12, shall not be less than 80 per cent.
- (ii) Form The material shall be in powder form.
- (iii) Residue on Sieving The residue on a 300 micron sieve, determined by (Particle Size) AS 3583.14, shall not exceed 2 per cent.

2. The properties which characterise the particular hydrated lime to be used in the stabilising agent submitted as part of the mix design are:

- (a) Percentage of calcium hydroxide
- (b) Fineness - Percentage by mass passing the 45 micron sieve (AS 2350.9).
- (c) Source.

C241.08 GROUND GRANULATED BLAST FURNACE SLAG

1. The ground granulated blast furnace slag shall conform to AS3582.2.
2. The properties which characterise the particular ground blast furnace slag to be used in the stabilising agent submitted as part of the mix design are:

Properties

- (a) Fineness - percentage by mass passing the 45 micron sieve (AS 2350.9).
- (b) Relative strength (28 days) (AS 3583.6).
- (c) Source.

C241.09 FLYASH

1. Flyash shall conform to AS3582.1.



Noosa Council

Contract No.

STABILISATION

C241.09 FLYASH cont.

2. The properties which characterise the particular flyash to be used in the stabilising agent submitted as part of the mix design are: **Properties**
 - (a) Fineness - percentage by mass passing the 45 micron sieve (AS 2350.9).
 - (b) Loss on ignition (AS 3583.3).
 - (c) Source.

C241.10 BLENDED STABILISING AGENTS

1. The Contractor may utilise a blended stabilising agent. The Contractor shall obtain mill and batch information which will make the blended stabilising agent traceable to the supplier's test results. Handling and storage requirements of the Supplier shall be complied with by the Contractor who shall also arrange for sampling of the agent as required by the Superintendent. **Requirements**
2. The mass of components of the nominated blended stabilising agent shall not vary by more than ± 3 per cent from the blend percentages nominated in the mix design described in Annexure C241A.
3. When a blended stabilising agent is produced from a combined grinding of components the following properties will characterise the particular stabilising agent blend: **Properties**
 - (a) Source of each component.
 - (b) Fineness - percentage by mass passing the 45 micron sieve (AS 2350.9).
 - (c) Setting time (AS2350.4).

C241.11 WATER

1. Water shall be free from harmful amounts of materials such as oils, salts, acids, alkalis and vegetable substances. The water shall not contain more than: **Quality**
 - (a) 600 parts per million of chloride ion, determined by AS3583.13
 - (b) 400 parts per million of sulphate ion, determined by AS 1289.4.2.1.
 - (c) 1 per cent by mass of undissolved solids.
2. Water accepted as potable and fit for human consumption will not require testing to confirm suitability. **Potable**

STABILISATION PROCESSES

C241.12 GENERAL

1. The Contractor shall submit details of the proposed equipment (including the mixing plant) and stabilisation procedures to be used in the work 14 days prior to commencement of the work. **Proposed Equipment and Procedures**



Noosa Council

Contract No.

STABILISATION

This submission, hereafter called the Work Plan, will nominate the sequence of operations, widths of stabilisation passes and provision for traffic if appropriate.

2. Notwithstanding submission to the Superintendent of the Contractor's equipment and stabilisation procedures, the work shall meet all the Specification requirements, and Statutory Requirements for Work Place Health and Safety, and the Contractor shall perform such tests as specified as the work proceeds, to ensure compliance. Costs of such tests shall be borne by the Contractor. **Compliance Contractor's Cost**
3. Stabilisation of pavement materials shall not proceed during wet weather or if rain is imminent and likely to occur during any stage of the stabilisation process so as to significantly influence the resultant moisture content and uniformity of moisture content in the mix. **Weather Conditions**

C241.13 APPLICATION OF STABILISING AGENT

(a) Stationary Mixing Plant

1. Application rate of stabilising agent shall be monitored at the pug mill or equivalent plant utilised as approved by the Superintendent. **Application Rate**
2. Application rate measured in kilograms per tonne of product shall be monitored and recorded for every 100 tonnes of production. **Measurement**
3. The achieved accuracy of application rate shall be ± 10 per cent of the nominated rate nominated in Annexure C241A.
4. The application rate shall not be allowed to exceed the nominated rate by more than 10 per cent. The stabilising agent incorporated in excess of the nominated rate shall be at no cost to the Principal. **Over Spread Contractor's Cost**

(b) In-Situ

1. The incorporation of stabilising agent is to follow a process where stabilising agent is spread on the pavement in advance of the specialist mixing equipment. Where special processes are proposed by the Contractor involving supply of stabilising agent within the mixing bowl of equipment the approval of the Superintendent is required and a demonstration of the process at Contractor's expense may be requested. **Application Process**
2. Spreading shall be carried out using the mechanical spreader nominated in the Work Plan and subsequently approved by the Superintendent. Annexure C241A nominates the spread rate **Spreading Rate**
3. The actual spread rate shall be within ± 10 per cent of the nominated rate. The Contractor shall verify this by testing the spread rate for each lot or 500m^2 of pavement treated (whichever is less) in each application of binder. Spread rate testing shall be performed by weighing the contents of a suitable 4 sided tray placed on the pavement and between the wheels of the mechanical spreader. The rate of stabilising agent spread shall be calculated by dividing the mass collected (kg) by the area of the tray (m^2). **Tolerances**

**C241.13 APPLICATION OF STABILISING AGENT cont****(b) In-Situ (cont)**

- | | |
|--|--------------------------------------|
| 4. Where spreading vehicles are fitted with load cells, the Contractor shall ascertain the average spreading rate of the stabilising agent by dividing the mass of the stabilising agent spread per run by the area of the run. The Contractor shall record this data for each run and make it available to the Superintendent promptly. Such action will not cancel the Contractor's obligation to undertake prescribed testing of spread rate if required by the Superintendent. | Load Cells |
| 5. The actual spread rate shall not exceed the nominated rate by more than 10 per cent. The stabilising agent spread in excess of the nominated rate shall be at no cost to the Principal. | Over Spread Contractor's Cost |
| 6. Spreading shall not proceed during windy conditions which may cause loss of stabilising agent or cause nuisance or danger to people or property. | Wind |
| 7. Traffic or equipment not involved in spreading or mixing of the stabilising agent shall not pass over the spread material until it has been mixed into the layer to be stabilised. | Construction Traffic |
| 8. Any spillage of the stabilising agent on site or at any loading location related to the site shall be removed as soon as possible and within the same work shift of such spillage. | Spillage |

C241.14 MIXING**(a) Stationary Mixing Plant**

- | | |
|--|--|
| 1. The stationary mixing plant shall be purpose built for the process of mixing road making materials. All equipment shall be maintained and calibrated so as to provide a uniformly mixed product without segregation of the aggregate material. | Equipment |
| 2. The plant shall provide for the controlled and metered inclusion of water into the mix. | Control of Water |
| 3. The stationary mixing equipment shall incorporate a delivery system for mix materials capable of producing a uniform mixture to design requirements. This performance shall be confirmed by monitoring of unconfined compressive strength of production, in accordance with AS 1289.6.1.1, with a pair of test specimens tested for each 400 tonnes of production and at full cost to the Contractor. | Uniform Mixture Contractor's Cost |

(c) In-situ

- | | |
|---|------------------|
| 1. Mixing equipment shall be purpose built for the process of in-situ mixing of road making materials. It shall be capable of mixing to the depth specified for the layer to be stabilised and of distributing the stabilising agent uniformly through the full depth and over the whole area of the layer to be stabilised. A minimum of 2 passes of the mixing equipment is required. As mixing blades or tynes wear shall be replaced so as to maintain mixing efficiency consistent with that demonstrated during trial section. The mixing equipment will be capable of supplying a calibrated amount of water to the mixing bowl in a such manner as to provide a uniformly moist mix to a target moisture content. | Equipment |
|---|------------------|



Contract No.



Cooloola Shire Council



Noosa Council

STABILISATION**C241.14 MIXING cont****(c) In-situ cont.**

2. The resultant mix shall be uniform over the full depth so that there are no lenses, pockets, lumps or granules of stabilising agent present in the layer or adjacent to it.
3. The procedure nominated in the Work Plan shall minimise disturbance of the distribution of stabilising agent spread in advance of the mixing process.
4. The Contractor shall carry out visual inspections during mixing to ensure uniform mixing is being achieved in the layer. Inspection results shall be recorded as cited in the Specification Part for Quality Requirements. The Superintendent and/or Council's Authorised Officer may require that additional passes by the mixing equipment be carried out to improve the visual uniformity of the mix and/or the moisture content. Such additional work shall be carried out at no cost to the Principal.

Uniform Mixture***Disturbance******Additional
Mixing
Contractor's
Cost*****C241.15 FIELD WORKING PERIOD**

1. The time period from addition of water during the mixing process until the completion of compaction is nominated as the Field Working Period. This period may vary significantly with variations in the type of stabilising agent.
2. The nominated Field Working Period shall be provided in Annexure C241A for the stabilising agent approved for the works. The Nominated Field Working Period shall be based on laboratory tests determining the time from mixing until such time as the calculated Wet Density for modified compaction procedures decreases by more than 2 percentage points. This testing shall be undertaken utilising AS 1289.5.7.1 and samples of the materials representative of those to be utilised in the works.
3. The Contractor will complete the compaction process within the Nominated Field Working Period unless specific approval is provided by the Superintendent to an adjustment for site and seasonal conditions.

Definition***Based on
Laboratory
Tests******Compaction
within Field
Working Period*****C241.16 TRIMMING AND COMPACTION**

1. After mixing the layer shall be trimmed and compacted in accordance with the Specification for MRS11.05 UNBOUND PAVEMENTS to produce a tight dense surface parallel with the finished wearing surface so that the levels do not vary from the design levels beyond the tolerance for primary trimming specified in Clause C241.18(a).
2. Subsequent secondary trimming may be undertaken on one or more occasions in preparation for primer seal and with the objective of meeting shape and level requirements. Secondary trimming shall involve cutting to waste. Work methods that lead to the development of laminations in the pavement will not be allowed and surface slurring will not be accepted. The Contractor's survey control methods as stated in the Work Plan will be adequate to ensure that the pavement layer thickness is not reduced during secondary trimming to an extent such that it fails to comply with the requirement for layer thickness in accordance with the tolerance specified in Clause C241.18(b).

Level Tolerance***Secondary
Trimming******Contractor's
Cost***



Contract No.



Cooloola Shire Council



Noosa Council

STABILISATION**C241.16 TRIMMING AND COMPACTION cont.**

When required by the Superintendent and/or Council's Engineer survey results shall be provided to confirm that the pavement layer thickness remains within tolerance after secondary trimming. This survey will be at no cost to the Principal.

- | | |
|---|----------------------------|
| 3. All trimmed material having been cut to waste shall be used as fill or spoiled as directed by the Superintendent. | Trimmed Material |
| 4. Measurements with a 3 metre straight edge shall be taken at a minimum of 10 randomly selected stations so as to represent each 200 metre lane length or part thereof. Deviation of the surface from the bottom of a 3 metre straight edge placed in any direction will meet the tolerance shown in Clause C241.18(a). This testing will be undertaken immediately prior to sealing or prior to agreed practical completion for any work component. | Straight Edge Test |
| 5. The stabilised layer shall be compacted over the entire area and depth so that the relative compaction determined by AS 1289.5.7.1 is not less than as detailed in the Specification for MRS11.05 UNBOUND PAVEMENTS, EARTHWORKS or STORMWATER DRAINAGE GENERAL as appropriate. | Compaction |
| 6. To provide true relative compaction assessments the lots shall be sampled and tested within the nominated field working period in accordance with AS 1289.5.7.1. | Test Method |
| 7. The maximum wet density (standard compaction) will be determined by sampling immediately after the determination of field density and testing will be undertaken within 2 hours of sampling. A determination of maximum wet density (standard compaction) representing the full layer depth is required for each sampling location when calculation of relative compaction is undertaken. | Wet Density |
| 8. The field density may be determined by in-situ sand replacement testing or by single probe Nuclear Density Meter in direct transmission mode in accordance with AS 1289.5.8.1. | In-Situ Dry Density |

C241.17 JOINTS

- | | |
|--|---------------------|
| 1. Joints are defined in this Specification to comprise interfaces between work episodes that are separated in time by more than the nominal field working period for the nominated stabilisation mix design. A longitudinal joint shall be considered to be a joint generally parallel to the road centreline. A transverse joint occurs when a length of work is terminated and extended at a later time after a period which exceeds the nominated field working period. | Joint Type |
| 2. All longitudinal and transverse joints shall be formed by cutting back into the previously stabilised and fully compacted sections. A minimum longitudinal overlap of mixing runs shall be 75mm. Transverse joints shall be overlapped by a minimum of 2 metres. The material disturbed during cutting back shall be remixed at full depth and incorporated into the new work. No longitudinal joints shall be allowed within 0.5 metre of the centreline of a typical wheelpath. | Cutting Back |
| 3. The level and shape of the joints shall be within the limits specified in Clause C241.18. | Finish |



Coooloolo Shire Council



Noosa Council

Contract No.

STABILISATION**C241.18 TOLERANCES****(a) Levels and Surface Trim**

- | | |
|---|---------------------------|
| 1. The surface level after primary trimming shall be within a tolerance of +30mm and +10mm of the levels shown on the Drawings. | Primary Trimming |
| 2. The surface level after secondary trimming shall be within a tolerance of +15mm and -15mm of the levels shown on the Drawings. | Secondary Trimming |
| 3. The pavement surface after secondary trimming and immediately prior to sealing shall be of a quality such that deviation under a 3 metre straight edge does not exceed 12mm. | |

(b) Layer Thickness

- | | |
|--|------------------------------|
| 1. The final thickness of the stabilised layer at any point shall be within a tolerance of +20mm and -10mm of the nominated layer thickness. | Minimum Thickness |
| 2. The average thickness of the layer in a lot shall be determined from measurements of six randomly selected locations over any 200m length of a lot. The average thickness shall not be less than that required to meet the specified final thickness tolerances after trimming. | Average Thickness |
| 3. The layer thickness shall be measured at the edges of the stabilising run before compaction commences. The layer thickness shall be measured relative to the finished design level. | Method of Measurement |

(c) Width

- | | |
|---|----------------------|
| 1. The width measured at any point of the stabilised layer shall be not less than the specified width as shown in the Drawings by more than 50mm. | Minimum Width |
| 2. The average width of the layer shall be determined from measurements at 3 sites selected at random by the Superintendent and/or Council's Engineer over any 200m length of a lot and shall be not less than the specified width. | Average Width |

C241.19 CURING

- | | |
|---|----------------------|
| 1. The Contractor shall submit to the Superintendent details of the proposed method of curing as part of the Work Plan. | Notice |
| 2. The stabilised work shall be protected against rapid drying out by keeping it continuously wet or damp during the period prior to the provision of a subsequent layer or the application of a prime or primer-seal. | Water Curing |
| 3. Water curing shall consist of frequent light uniform spraying that will not produce significant run off or flooding on sections of the area. Slurrying of the surface or leaching of the stabilising agent shall be avoided. | Caution |
| 4. Under this Specification provision for curing up to the period indicated in Annexure C241A shall be the responsibility of the Contractor at cost to the Contractor. | Curing Period |



Contract No.



Cooloola Shire Council



Noosa Council

STABILISATION

LIMITS AND TOLERANCES

C241.20 SUMMARY OF LIMITS AND TOLERANCES

1. The limits and tolerances applicable to the various clauses of this Specification are summarised in Table C241.3 below:

Item	Activity	LimitsTolerances	Spec Clause
1.	Quicklime		
	a) Available Lime	>85% Calcium Oxide content	C241.06
	b) Slaking Rate	Active Slaking time < twenty minutes, and temperature rise on slaking not less than 40°C in six minutes (for an average of four samples).	C241.06
	c) Particle Distribution	Fraction passing AS Sieve: 100% for 13.2mm Sieve 96-100% for 9.5mm Sieve 70-100% for 4.75mm Sieve 0-90% for 2.36mm Sieve	C241.06
2.	Hydrated Lime		
	a) Available Lime	>80% Calcium Hydroxide	C241.07
	b) Particle Size	<2% residue on a 300 micron Sieve	C241.07
3.	Blended Stabilising Agents	Blend percentages shall not vary by more than $\pm 3\%$ from those nominated in Annexure C241A	C241.10
4.	Water		
	a) Chloride ion content	<600 PPM Chloride ion	C241.11
	b) Sulphate ion content	<400 PPM Sulphate ion	C241.11
	c) Undissolved solids	<1 percent by mass of undissolved solids	C241.11
5.	Application of Stabilising Agent		
	a) Spread Rate or Incorporation Rate for in-situ plant.	Actual spread rate shall be within $\pm 10\%$ of the nominated rate	C241.13



Noosa Council

Contract No.

STABILISATION

LIMITS AND TOLERANCES cont.

C241.20 SUMMARY OF LIMITS AND TOLERANCES cont.

Item	Activity	LimitsTolerances	Spec Clause
6.	Trimming and Compaction		
	a) Surface Level	After primary trimming be within +30mm and +10mm of levels shown on Drawings After secondary trimming be within ± 15 mm of levels shown on Drawings	C241.18(a)
	b) Layer Thickness	Final thickness of layers shall not vary more than +20mm and - 10mm of required thickness	C241.18(b)
	c) Shape	Shall not deviate more than 12mm under a 3m straight edge immediately prior to first sealing	C241.18(a)
7.	Joints		
	a) Longitudinal Overlap	> 75mm overlap of mixing runs	C241.17
	b) Transverse Overlap	> 2m overlap of transverse joints	C241.17
	c) Longitudinal Joints	Shall not be allowed within 0.5m of the centreline of a typical wheelpath	C241.17
8.	Width		
	a) Width of Stabilised Layer	At any point, the width shall be not less than 50mm short of the width shown on the Drawings with an average width always greater than that shown on the Drawings.	C241.18(c)

Table C241.3 - Summary of Limits and Tolerances



Contract No.



Coooloolo Shire Council



Noosa Council

STABILISATION

SPECIAL REQUIREMENTS

C241.21 RESERVED

C241.22 RESERVED

C241.23 RESERVED

MEASUREMENT AND PAYMENT

C241.24 PAY ITEMS

1. Payment shall be made for the activities associated with completing the work detailed in this Specification for on-site stabilisation in accordance with Pay Items C241.24(a) to C241.24(b) inclusive. Except that where stabilisation is provided by use of stationary plant the supply of the material including the stabilisation service and stabilising agent is measured and paid in accordance with Specification for FLEXIBLE PAVEMENTS or EARTHWORKS as appropriate for supply of the material as a pre-mix product. Supply in these circumstances includes all testing.
2. A lump sum price for any of these items shall not be accepted.
3. Supply, spread and compact subbase, or base material is measured and paid in accordance with the Specification of MRS11.05 UNBOUND PAVEMENTS.
4. Supply, spread and compact select material is measured and paid in accordance with the Specification for EARTHWORKS.
5. Control of traffic is measured and paid in accordance with the Specification for CONTROL OF TRAFFIC.
6. If any item for which a quantity of work is listed in the Schedule of Rates has not been priced by the Contractor, it shall be understood that due allowance has been made in the prices of other items for the cost of the activity which has not been priced.

Pay Item C241.24(a) SUPPLY AND SPREAD STABILISING AGENT (IN-SITU MIXING ONLY)

1. The unit of measurement shall be the square metre.
2. The area shall be determined by the length and width of work as specified on the Drawings or as directed by the Superintendent.
3. No account shall be taken of allowable tolerances.
4. The schedule rate under this Pay Item shall include all the activities associated with the supply, delivery and spreading of the stabilising agent including testing in accordance with this Specification.



Coastal Shire Council



Noosa Council

Contract No.

STABILISATION

Pay Item C241.24(b) MIXING OF STABILISING AGENT

1. The unit of measurement shall be the square metre.
2. The area shall be determined by the length and width of work as specified on the Drawings or as directed by the Superintendent.
3. No account shall be taken of the allowable tolerances.
4. The schedule rate under this Pay Item shall include all the activities associated with the mixing of the stabilising agent with the designated materials in-situ and to the nominated depth in accordance with this Specification.

ANNEXURE C241A
STABILISATION MIX DESIGN

Type of Stabilising Agent

.....

.....

Nominal Percentage of Stabilising Agent by Mass %

Spread Rate of Stabilising Agent for contractual purposes (kg/m²)

Depth of Compacted Layer to be Stabilised (mm)

Nominated Field Working Period (hrs)

Nominated Target Unconfined Compressive Strength (UCS)
(7 day accelerated curing) MPa

Nominated Target CBR Value (4 day soaked) for stabilised
modified subgrade %

Period for Contractor's Curing (days)

Nominated Granular Material(s) (type)

Source of Nominated Granular Material