

NOTES:

- (i) Equivalent fluid density of soil 6.7kN/m³ (maximum) (ii) Safe bearing capacity of soil - 100kPa (minimum) shown.
- Mortar to be grade M3 in accordance with AS3700.
- slump of 230±30.
- Reinforcement symbols (i) N Hot rolled deformed bar millimetres.
- (ii) SL Hard drawn wire fabric (square) fsy=500MPa

- 10. Mortar fins protruding into cores to be removed before grouting.
 - to ensure that the cores are completely filled.
- any horizontal joint in the blockwork.
- height of approximately 200 above ultimate ground level.
- 14. All compact clay material to be suitably selected non-dispersive.
- weephole.
- manufacturers fittings.
- adhered to both sides.
- days after wall construction and aroutina.
- 21. All dimensions in millimetres.
 - specified in construction documents.

RETAINING WALLS CONCRETE BLOCK TYPE 1 AND TYPE 2 FOOTINGS

1. The retaining wall design provided assumes the following design loads. Seek advice from a suitably gualified RPEQ where site conditions differ from that

Concrete blocks to be grade 15 in accordance with AS1122.
Mortar to be grade M3 in accordance with AS3700.

4. Concrete footings to be grade N25 in accordance with AS1379.

5. Grout to be grade N20 in accordance with AS3700 with 10mm aggregate and a

fsy=500MPa The number following the symbol for a bar, is the diameter of the bar in

Provide minimum 50mm cover to all reinforcement unless noted otherwise.

Provide clean-out block at bottom of each vertical pour.

Vertical reinforcement to be tied in its correct position to the bottom starter bars via the clean-out openings and held in position at the top.

11. All cores to be filled with grout, whether reinforced or not. Grout shall be rodded

12. For halts in placing, the level of the grout shall be located at least 50mm from

13. Install weepholes in addition to the longitudinal drain for maintenance and overflow purposes. Weepholes to be a vertical joint void of mortar on the lower half of the joint, spaced at approximately 1000 max. centres and positioned at a constant

15. Longitudinal drain shall be 300 x 50 megaflow to 100 dia. corrugated perforated polyethylene pipe, encased with geofabric (BIDIM A20 or equivalent). The invert of -Geotextile wrapped around the longitudinal drain shall be 100 below the invert of the weephole inlet.

Preferably the longitudinal drain shall outlet to the a suitable location as

determined by MBRC superintendent at a minimum slope of 1 in 250 and at 25m intervals. Where such an outlet is not achievable, the inverts of the longitudinal drain and the weephole inlet shall be aligned to allow direct discharge via the

16. All connections, including the joining of lengths of strip drain shall be made using

17. 300mm thick, free draining filter sand/gravel layer separated from insitu material by a type 2 geofabric layer. Alternatively, drainage layer for full height and length of wall to be cordrain or equivalent with geofabric (BIDIM A29 or equivalent)

18. Backfill shall be free draining, non-plastic predominately granular material with minimum friction angles of 38° and 27° where founding materials are sand or other materials respectively. Do not place backfill behind the wall until at least 10

19. Provide rendered capping only where capping to the top of wall is specified. 20. All Council retaining walls are to be constructed in the road reserve where possible. Private wall including footing to be contained wholly within private property.

22. Plain concrete finished retaining walls are unacceptable. Appropriate finish to be

23. Waterproofing membrane installed to all block walls in accordance with AS4654.

Moreton Bay Regional Council

SL-1040

Α3

ORIGINAL SIZE

REVISION

B